11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities for the extension of Glass House in Lal-Bagh, Bangalore.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavation	C.yds.		71	
2	Jelly concrete in mortar	C.ft.		392	
3	Burnt stone in mortar	,,		1,523	
4	Burnt stone slabs roughly dressed 6″ thick ..	Sq. ft.		56	
5	Burnt stone slabs nicely dressed 6″ thick ..	,,		400	
6	Cast iron pillars—				
	(*a*) End pillars 6″ dia. with base and capital step thickness $\frac{1}{2}$″ × 15$\frac{1}{2}$′ in height ..	Cwts.		192$\frac{1}{3}$	
	(*b*) Centre pillars 8″ dia. thickness $\frac{5}{8}$″ with base and capitals 17′ in height				
7	T. iron bends to roof—				
	Centre and ends	,,		28	
8	Joists 3″ × 4″	,,		69	
	Bressummer (7″ × 4″)				
9	L. Angle purlins	,,		29	
	T. Rafter to fix glasses				
10	Bending T. iron giving them with fish plate, bolts etc., complete	L.S.		..	
11	Roofing with corrugated zinc sheets and fixing in the bolts and nuts	Sq.		32.80	
12	Roofing $\frac{1}{4}$″ plate glasses	S.ft.		820	
13	Zinc Ridge	R.ft.		82	
14	Ornamental cast iron ridge railing	,,		82	
15	Ornamental plate glass frame work for gables	S.ft.		220	
16	Teak wooden cornice block alround Brassummer	,,		240	
17	Repairing and refixing ornamental cast iron railings between pillars over retaining wall ..	R.ft.		162	
18	Cast iron circular ornamental lockets over centre pillars (3′ diameter)	Each		16	
19	Cast iron circular ornamental lockets between pillars (3′ diameter)	One		40	
20	Painting Girders	L.S.		50.00	
21	Cement pointing to basement	Sq.		12.00	
22	Cleaning side and levelling ground	L.S.		..	
23	Gravelling and sanding	,,		..	
24	Ornamental cast iron finials as per existing design	No.		2	
25	Other unforseen items during execution such as scaffolding, etc.	R.S.		..	

A. TANDONI RAO,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification, dated 23rd July 1934.

The attention of the public is hereby invited to the detailed notification inviting tenders for the maintenance work of Nittur Major Tank, Register No. 43, Malvalli Taluk, published on pages 986-987 of Parts VI of the *Mysore Gazette*, dated 2nd August 1934.

The last date for the receipt of tenders is 2 P.M., on 13th August 1934.

The earnest money to accompany the tender is Rs. 150.

M. A. SRINIVASACHARI,
Executive Engineer.